

TENDER DOCUMENT

Project: Multi-Storied Residential Building - Phase 2

Location: Bangalore, Karnataka

Date: March 1, 2026

Tender No: TND/2026/001

SECTION 1: SCOPE OF WORK

The scope of work includes design, supply, and delivery of all materials required for the structural and finishing works of the basement and ground floor of the proposed building as per drawings and specifications attached.

SECTION 2: STRUCTURAL WORKS

Item	Description	Qty	Unit	Specification
1	M30 concrete for foundation	120	m³	IS 456, OPC 53 grade
2	M35 concrete for columns	80	m³	IS 456, OPC 53 grade
3	M25 concrete for slabs	200	m³	IS 456, OPC 53 grade
4	M25 concrete for beams	100	m³	IS 456, OPC 53 grade
5	Fe550 TMT bars 20mm dia	8000	kg	IS 1786, Fe550 grade
6	Fe550 TMT bars 16mm dia	6000	kg	IS 1786, Fe550 grade
7	Fe550 TMT bars 12mm dia	4000	kg	IS 1786, Fe550 grade
8	Fe550 TMT bars 8mm dia	3000	kg	IS 1786, Fe550 grade
9	Structural steel plates 10mm	1500	kg	IS 2062, E250 grade
10	First class brickwork 230mm	300	m³	IS 1077

SECTION 3: FINISHING WORKS

Item	Description	Qty	Unit	Specification
11	External plastering 20mm	1500	m²	Cement mortar 1:4
12	Internal plastering 15mm	2500	m²	Cement mortar 1:4
13	Wall putty 2 coats	2500	m²	Birla putty
14	Premium emulsion paint	3000	m²	Asian/Berger/ICI
15	Texture paint accent wall	200	m²	Asian/Berger
16	Ceramic wall tiles 300x450mm	800	m²	IS 13630
17	Granite counter top	50	m²	20mm Black Galaxy

SECTION 4: FLOORING AND WOODWORKS

Item	Description	Qty	Unit	Specification
18	Vitrified tiles 800x800mm	1200	m²	IS 15622
19	Granite flooring 18mm	300	m²	Kashmir White
20	Wooden flooring laminate	150	m²	8mm AC3 rated
21	Plywood flush door 35mm	25	nos	IS 2191 Plywood
22	WPC door frame	25	nos	75mm section
23	Aluminum windows	50	nos	Anodized 1.2mm
24	Glass panes 6mm	120	m²	Tinted float glass

SECTION 5: MEP WORKS

Item	Description	Qty	Unit	Specification
25	Electrical conduit 25mm PVC	1000	rm	IS 9537
26	Electrical wires 2.5mm FR	3000	rm	IS 694
27	DB box 24 way	5	nos	Metal enclosure
28	CPVC pipes 32mm dia	500	rm	IS 15778
29	UPVC pipes 110mm SWV	200	rm	IS 13592
30	Sanitary ware set complete	20	set	Cera/Jaguar/Parryware

SECTION 6: SPECIAL ITEMS

Item	Description	Qty	Unit	Specification
31	Waterproofing for basement	800	m²	K11 BASF/Bituguard
32	Fire alarm system	1	set	Addressable type
33	CCTV surveillance	1	set	16 channel DVR
34	EPS insulation 50mm	400	m²	Density 32 kg/m³
35	False ceiling Gyproc	600	m²	12.5mm gypsum

SECTION 7: TECHNICAL SPECIFICATIONS

Concrete: All concrete shall be design mix M30/M35 as per IS 456. Minimum cement content 320 kg/m³.

Steel: TMT bars Fe550 grade conforming to IS 1786. Yield strength 550 MPa.

Brickwork: First class bricks IS 1077. Mortar 1:4. All reinforcement as per structural drawings.

Plastering: Curing for 7 days. Thickness as specified. Key coat on RCC surface.

Flooring: All tiles from BIS approved manufacturers. Pattern as per drawings.

SECTION 8: TERMS AND CONDITIONS

- Rates are ex-works. GST extra.
- Delivery: 45 days from PO.
- Payment: 30% advance, 70% on delivery.
- LD: 0.5% per week delay, max 5%.
- Warranty: 12 months from completion.