

REQUEST FOR QUOTATION

Project: Commercial Complex - Interior Works
Location: Mumbai, Maharashtra
Date: February 10, 2026

1. SCOPE OF SUPPLY

Complete supply and delivery of materials for interior construction works as per specifications below.

2. ITEMS REQUIRED

Item	Description	Qty	Unit	Spec
1	Ceramic floor tiles 600x600mm	800	m ²	IS 13630
2	Granite flooring 18mm thick	150	m ²	Black Galaxy
3	Aluminum false ceiling	400	m ²	Powder coated
4	Gypsum board ceiling 12mm	350	m ²	Moisture resistant
5	Emulsion paint 2 coats	1200	m ²	Asian/Berger
6	Enamel paint for woodwork	200	m ²	IS 133
7	Electrical conduit 25mm PVC	500	rm	IS 9537
8	CPVC pipes 25mm dia	300	rm	Ashirvad/Supreme
9	PVC door frames 750x2000mm	15	nos	WPC frame
10	Glass panes 5mm clear	100	m ²	Float glass
11	Stainless steel railing	50	rm	SS 304 grade
12	Fire exit signage	20	nos	As per NBC
13	M25 concrete for slabs	100	m ³	IS 456
14	Fe500 steel reinforcement	5000	kg	IS 1786
15	Brickwork for partitions	80	m ³	IS 1077

3. SPECIFICATIONS

Floor Tiles: First quality ceramic tiles conforming to IS 13630. Size 600x600mm. Water absorption less than 0.5%.

Granite: Black Galaxy granite, minimum 18mm thick, polished on all sides. Tolerance ± 1 mm on dimensions.

False Ceiling: Aluminum T-bar grid with gypsum board tiles 600x600mm. Main runners at 1200mm c/c.

Painting: All surfaces to be thoroughly cleaned and primed. 2 coats of premium emulsion paint.

Electrical: All conduit and wiring as per IS standards. PVC conduit 25mm dia minimum.

Plumbing: CPVC pipes and fittings for hot/cold water. Working pressure 10 bar.

4. TERMS AND CONDITIONS

- Prices should be exclusive of GST.
- Delivery to site within 21 days.
- Inspection by Quality Engineer before acceptance.
- Payment: 40% advance, 60% on delivery.

5. QUALITY REQUIREMENTS

All materials shall be from approved manufacturers with BIS certification. Test certificates to be furnished.

6. MEASUREMENT AND PAYMENT

Measurement based on net quantities delivered and accepted. No allowance for wastage.