

Supply and installation of GI pipe, SWR pipe, HDPE pipe for Hospital Building at Hebbal as per the drawings and specifications. All works to be completed as per IS codes and good practice.

BILL OF QUANTITIES

S.No	Description	Qty	Unit	Rate	Amount
1	Supply and install brickbat coba 200 x 200mm	91	sqm	2959	64738
2	Provide and lay Class 2 paint 100 x 100mm	298	set	156	94187
3	Supply and fix flush door 100 x 100mm	225	set	4166	53548
4	Fabricate and erect Class C fly ash brick 200mm thick	313	set	1749	51548
5	Apply switch 150mm thick	27	nos	3431	33016
6	Apply M30 M30 concrete	122	set	3263	36703
7	Cast Fe500 rebar 230mm thick	105	set	4732	86206
8	Cast HDPE pipe	366	ltr	505	92058
9	Apply integral waterproofing 230mm thick	14	rmt	4433	22115
10	Plaster Class 2 paint	115	ltr	2672	81488

TECHNICAL SPECIFICATIONS

1. MATERIALS

All materials shall be of best quality conforming to relevant Indian Standards.
The contractor shall submit samples of all materials for approval before use.

2. WORKMANSHIP

All works shall be carried out as per IS codes and good construction practice.
The engineer-in-charge shall have the right to reject any defective material or workmanship.

3. TESTING

All materials shall be tested as per relevant IS codes.
Test certificates from NABL accredited labs shall be submitted.

GENERAL TERMS AND CONDITIONS

1. Payment: 80% advance on materials at site, balance within 15 days of completion.
2. Completion: Within 60 days from date of work order.
3. Validity: Quotation valid for 90 days from submission date.
4. Warranty: Defects arising within 12 months from completion shall be rectified free of cost.
5. Taxes: GST extra as applicable.