

2.18.17. ACOUSTIC INSULATION

Complies for
density of 180-220

- Material shall be engineered Nitrile Rubber open cell foam.
- The Random Incidence Sound Absorption Coefficient (RISAC); tested as per ISO 354.
- The material should be fibre free.
- The density of the same shall be within 140-180 Kg/m³.
- It should have Microban®*; antimicrobial product protection and should pass Fungi Resistance as per ASTM fi 21 and Bacterial Resistance as per ASTM E 2180.
- The material should have a thermal conductivity not exceeding 0.047 W/m.K @ 20°C
- The material should withstand maximum surface temperature of +85 Deg.C and minimum surface temperature of -20 Deg.C
- The insulation should pass Air Erosion Resistance Test in accordance to ASTM Standard C 1071-05 (section 12.7)

PROCEDURE:

The inside surface for the ducts shall be covered with adhesive recommended by the manufacturer. Cut Foamed sheets into required sizes apply adhesive on the foam and stick it to the duct surface.

2.19. NOISE AND VIBRATION CONTROL

2.19.1. SCOPE

The scope of these specifications comprises of the supply & erection of noise and vibration isolation equipment as called for in the Bill of quantities and Equipment schedule.

2.19.2. GENERAL SPECIFICATIONS

- All vibration control equipment shall meet the intent of specifications.
- Any request for changes or modifications in the specifications must be submitted in writing in time for review, approval and issuance through a written addendum to the specifications, prior to price bid opening.
- The contractor shall be responsible for verifying the completeness of the isolation requirements and the correctness and overall suitability of the equipment to meet the intent of specifications. Equipment needed to meet these requirements, even if, specifically not mentioned herein or shown on the drawings, shall be supplied by the contractor without claim for additional payment.
- The minimum static deflection of each vibration isolation unit and unit type and unit base type shall be as shown in the equipment schedule or as specifically required.