

Sr. No.	Description	UNIT	Total Qty
F	THERMAL & ACOUSTIC INSULATION:		
1	Supply, installation, testing and commissioning of first layer of closed cell nitrile rubber insulation on SA duct, RA duct & TFA duct of Armaflex (FM approved) including adhesive required for insulation application ,fixing of black tap as per specifications. Density of insulation shall be between 40 to 50 Kg/m3.		
1.1	19mm thick - SA/DH-AHU/TFA duct	Sqmtrs	14735
1.2	32mm thick with 7 mill glass cloth and special UV resistant paint/weatherproof coating for the exposed ducting - SA/DH-AHU	Sqmtrs	18

Comply