



MATERIAL INDENT FORM

FORMAT NO. : 020 : IV : D : 28
DATE : 2.08.25
REV. NO. : 0
PAGE : 1 OF 62

MAT. COD E	Sr No	DESCRIPTION	UNIT	MATERIAL CONTRACT QTY.	CONSTRUCTION		Est Amount	ENGINEERING DELY. REQD.	Compliance	
					REQD. QTY.	EST. Rate				
F	A)	Piping								
	1.0	CHILLED WATER PIPING AND INSULATION								
	1.1	Supply, installation, testing & commissioning of insulated MS Class C chilled water piping as per IS1239 / IS 3589 . Piping shall be pre-fabricated from MS pipes as specified in technical specifications and insulated with Class O closed cell elastomeric nitrile rubber insulation. The nitrile rubber insulation shall be factory laminated with woven Fibreglass fabric sheet of 0.18 mm thickness and coated with acrylic polymers or blends on one side and with self adhesive backing on the other. Insulation over 25mm thickness shall be installed in multiple layers with staggered seams. Insulation shall be installed at site and shall be supplied with insulation tapes to tide over insulation seams. Piping shall complete with fittings, bends, elbows, hot-dipped galvanized supports, vibration isolators, GI fasteners, tees, reducers, mating flanges & sockets for BAS, and sleeves as per specifications. Contractor shall prepare shop drawings with the intent to prefabricate piping in pieces of suitable length as per drawing at an offsite workshop , and supplied to site with matching PN16 flanges on either side for rapid assembly at site. This fabrication shall be as per approved shop drawing with each piece clearly identified and tagged for installation. Pieces fabricated will be marked with the same number when supplied to site. Pipe pieces shall be assembled at the workshop in suitable lengths, pressure tested before supply. Pressure testing at workshop shall be witnessed by Client representative / Project management team with intimation in advance . Pipes thus tested will be disassembled and transported to site with clear tagging. Please refer specifications for further details. Separate colour bands of 50 mm PVC tapes to be used for supply and return piping. All accessories used shall be hot dipped Galvanised. During execution phase, Supply and Return pipes shall be installed with respective identification tags prominently visible. This shall be followed without any deviation. After final insulation the entire length of piping shall be finished with 24G Al cladding . Entire network of piping to be tested at site for 10kg/cm2 (Air & water both) before insulation work and to be recorded/witnessed by client and representatives							Comply	
		SUPPLY PIPES @ 19 DEG CAT LOWER FLOOR								
	a	300mm dia. 32mm thick insulation	Rmt	15						
	b	250mm dia. 32mm thick insulation	Rmt	185						
	c	65mm dia. 25mm thick insulation	Rmt	110						
	d	50mm dia. 25mm thick insulation	Rmt	35						
	e	40mm dia. 19mm thick insulation	Rmt	30						
	f	32mm dia. 19mm thick insulation	Rmt	135						
	g	25mm dia. 19mm thick insulation	Rmt	40						
		RETURN PIPES @ 27 DEG CAT LOWER FLOOR								
	a	300mm dia. 32mm thick insulation	Rmt	15						
	b	250mm dia. 32mm thick insulation	Rmt	185						
	c	65mm dia. 25mm thick insulation	Rmt	110						
	d	50mm dia. 25mm thick insulation	Rmt	35						
	e	40mm dia. 19mm thick insulation	Rmt	30						
	f	32mm dia. 19mm thick insulation	Rmt	135						
	g	25mm dia. 19mm thick insulation	Rmt	40						
	3.0	Providing and fixing nitrile rubber insulation on condensate water drain pipes.								
	b	65 mm dia (19 mm thickness)	Mtrs	200						
	c	32 mm dia (13 mm thickness)	Mtrs	30						
	d	25 mm dia (9 mm thickness)	Mtrs	390						
	2	CHILLED WATER PIPING AND INSULATION								
	2.1	Pipline on Terrace								
		Supply, installation, testing & commissioning of insulated MS Class C chilled water piping as per IS1239 / IS 3589 . Piping shall be pre-fabricated from MS pipes as specified in technical specifications and insulated with Class O closed cell elastomeric nitrile rubber insulation. The nitrile rubber insulation shall be factory laminated with woven Fibreglass fabric sheet of 0.18 mm thickness and coated with acrylic polymers or blends on one side and with self adhesive backing on the other. Insulation over 25mm thickness shall be installed in multiple layers with staggered seams. Insulation shall be installed at site and shall be supplied with insulation tapes to tide over insulation seams. Piping shall complete with fittings, bends, elbows, hot-dipped galvanized supports, vibration isolators, GI fasteners, tees, reducers, mating flanges & sockets for BAS, and sleeves as per specifications. Working pressure of the chilled water pipe shall be suitable to PN 16 rating. Contractor shall prepare shop drawings with the intent to prefabricate piping in pieces of suitable length as per drawing at an offsite workshop , and supplied to site with matching PN16 flanges on either side for rapid assembly at site. This fabrication shall be as per approved shop drawing with each piece clearly identified and tagged for installation. Pieces fabricated will be marked with the same number when supplied to site. Pipe pieces shall be assembled at the workshop in suitable lengths, pressure tested before supply. Pressure testing at workshop shall be witnessed by Client representative / Project management team with intimation in advance . Pipes thus tested will be disassembled and transported to site with clear tagging. Please refer specifications for further details. Separate colour bands of 50 mm PVC tapes to be used for supply and return piping. All accessories used shall be hot dipped Galvanised. During execution phase, Supply and Return pipes shall be installed with respective identification tags prominently visible. This shall be followed without any deviation. After final insulation the entire length of piping shall be finished with 24G Al cladding. Entire network of piping to be tested at site for 10kg/cm2 (Air & water both) before insulation work and to be recorded/witnessed by client and representatives. All								Comply
		Quoted price shall include Supply & Fixing of Hot dip Galvanised MS fabrication works involving MS I-beam/Angles, C-Channels/MS-Flats etc. as required for supporting the Piping including of Chiller Bypass loop on the terrace as per approved drawing including all cutting, welding, cleaning, hot-dip galvanised as specified at off-site workshop and transpoorting to site.								
		SUPPLY PIPES @ 19 DEG CAT TERRACE EXPOSED								
	a)	200 mm dia (32mm thick insulation)	Rmt	30						
		RETURN PIPES @ 27 DEG CAT TERRACE EXPOSED								
	b)	200 mm dia (32mm thick insulation)	Rmt	30						
		TOTAL		1780						
	B)	SPECIFICATIONS ATTACHED								
	C)	ADDENDUM								
	1	Kindly refer attached addendum								
	2									
	OTHER INSTRUCTIONS : * G.A. DRGS. REQD. FOR APPROVAL/INFORMATION. -Yes , TDS, GA DWGS * DATA SHEET REQD. FOR APPROVAL/INFORMATION. -YES * QUALITY ASSURANCE PLAN REQD. FOR APPROVAL/INFORMATION. * FINAL INSPECTION/STAGE INSPECTION BEFORE DESPATCH. * TEST CERTIFICATE REQD; O&M MANUAL REQD. * LOT - I/II/III/IV/ADDITIONAL ORDER FOR VARIABLE ITEMS.									
JOB NAME - MEP Works for NTT Data Center, Phase 2						ORDER DATE	:			
ADDRESS - Noida, Uttar Pradesh						COMPLETION	:			
						PAGE NO.	:			